

**TOWN OF MIDDLESEX**  
**REQUEST FOR PROPOSALS:**

**FLOOD REPAIR & MITIGATION ON DAVY, UPPER SUNNY BROOK & BOLDUC ROADS**

**SPEC SHEET \***

**DAVY ROAD:**

Ditching	1,000 LF
Seed/mulch	500 LF
Ditch stone	500 LF
18" cross culvert	40 LF
Ledge removal	8 hours
1 ¼" plant mix	200 CY (12' x 1,500' x 4")
Grade & Compact	

**UPPER SUNNY BROOK ROAD:**

Ditching	2,000 LF
Ditch stone	1,500 LF
Hydro/seed/mulch	500 LF
18" cross culvert	40 LF
Ledge removal	8 hours
3" dense grade	70 CY (5-14 CY loads)
1 ¼" plant mix	350 CY (14' x 2,000' x 4")

End of road at Town turn around, fill ditch in completely with ditch stone for approximately 75' x 2' x 2' = 11 CY

**BOLDUC ROAD:**

Stone fill at 4' culvert	12" – 18"
Inlet & outlet	14 CY

\*Bid quantities may be adjusted to meet field conditions by Road Foreman Eric Metivier